Fifth Floor (Bay B)

Remove ptd. galv. cap flashing; provide alum. flashing w/ drip edge; extend step flashing min. 8” behind slate.

Scrape existing trim; provide preservation epoxy as required; paint white.

Remove slate prior to sheet metal work at dormers and reinstall. Provide sound new slates to match existing as required under Unit Prices Section 01026.

Scrape existing trim; provide preservation epoxy as required; paint white.

Remove ptd. galv. cap flashing; provide alum. flashing w/ drip edge; extend step flashing min. 8” behind slate.

Cornice repair and replacement. See detail on SK-5-4.